



**NOTES:**

1. SIDE SEWER STUBS SHALL BE INSTALLED TO EACH BUILDING LOT DURING PLAT CONSTRUCTION. WHEN A LOT IS BUILT ON, THE SIDE SEWER CONNECTION SHALL BE COMPLETED AS SHOWN IN CITY STANDARD DETAIL NO. 04.03.03.
2. THE TOP ONE (1) FOOT OF THE 2X4X4'-0" LONG PRESSURE TREATED SIDE SEWER MARKER SHALL BE EXPOSED, AND SHALL BE PAINTED TRAFFIC YELLOW AND THE DEPTH PAINTED IN BLACK ON BOTH SIDES OF THE MARKER.
3. NINE (9) GAUGE GALVANIZED WIRE TO BE ATTACHED TO THE 2X4X12 CLEAT AND ATTACHED TO THE MARKER POST ABOVE FINISHED GRADE.
4. IN LOCATION WHERE SIDEWALKS ARE NOT PRESENT NOR REQUIRED THE CONTRACTOR SHALL POUR A CONCRETE COLLAR AS DIRECTED BY THE CITY ENGINEER. SEE CITY STANDARD DETAIL NO. 04.03.05 FOR FRAME AND COVER INFORMATION.
5. END OF SIDE SEWER SHALL HAVE A FIVE (5) FOOT MINIMUM COVER AT THE PROPERTY LINE.
6. SEWER PIPE TRENCHING, BEDDING AND BACKFILL SHALL CONFORM TO CITY STANDARD 06.01.01.



**CITY OF PUYALLUP**  
 OFFICE  
 of  
 THE CITY ENGINEER

APPROVED FOR PUBLICATION



DATE SEALED: 3/19/2020

**SIDE SEWER STUB WHEN  
 UTILITY EASEMENT DOES  
 NOT EXIST**

(NOT TO SCALE)

FILE NAME: Y:\SHARED\DRAWINGS\CITY STANDARDS\2018\02 - PART 2 - STANDARD DETAILS\CAD\400\04.03

CITY STANDARD  
**04.03.02**