



NOTES:

1. SAMPLING CONNECTION SHALL BE INSTALLED OUTSIDE WITH UNOBSTRUCTED ACCESS AT ALL TIMES.
2. SAMPLING CONNECTION SHALL BE INSTALLED FOR EACH COMMERCIAL / RETAIL UNIT OR SPACE.
3. CLEAN OUT AND SAMPLING CONNECTION COVERS:
 - A) FOR NON-VEHICULAR TRAFFIC INSTALLATIONS USE "CARSON" MODEL 910 GREEN YARD BOX WITH BOLT DOWN LID MARKED SEWER OR APPROVED EQUAL.
 - B) FOR ASPHALT, GRAVEL, OR TRAFFIC INSTALLATIONS, SEE CITY STANDARD DETAIL NO. 04.03.05 FOR FRAME AND COVER SECTION.
4. EACH CLEANOUT ASSEMBLY SHALL CONSIST OF: ONE CLEANOUT ADAPTER, HUB x FEMALE, FIPT, PVC SI AND ONE CLEANOUT PLUG, MOPT WITH RAISED NUT, PVC SDR35.



CITY OF PUYALLUP
 PUBLIC WORKS AND
 DEVELOPMENT
 ENGINEERING

APPROVED FOR PUBLICATION



DATE SEALED: 7/6/23

**COMMERCIAL SIDE SEWER
 CONNECTION WITH SAMPLING
 CONNECTION**

(NOT TO SCALE)

CITY STANDARD
 04.03.04

FILE NAME: Y:\SHARED\DRAWINGS\CITY STANDARDS\2018\02 - PART 2 - STANDARD DETAILS\CAD\00 01.03